

SECTION 9: CASESTUDIES

9.1 CASESTUDIES

9.1.2 PANDI

CUSTOMER: PANDI

LOCATION: GLAXO SMITH KLINE UK LTD, 980 GREAT WEST ROAD, BRENTFORD, MIDDLESEX, TW8 9GS

PROJECT BRIEF: The installation of approximately 20,000 outlets from a total 50,000 outlet installation. **This project was the largest new build site undertaken anywhere in the UK during 2001.**

NO. OF OUTLETS: Approx 20,000

THE INSTALLATION: DWM were involved in the installation and preparation, and contributed heavily in the success of the overall installation, supplying a 24 hour rotating shift crew of 15-18 staff over a 5 month period.

The company stretched its already experienced understanding of Project Management, Health & Safety, Method Statements, Risk Assessments and Building Site Regulations.

This installation was an embryo idea from both the main contractor PANDI and the product supplier KRONE. It was a single ended pre-terminated CAT6 Solution with outlet FOBs of 4 being pre-terminated and installed via pre-labelled, cut to length FOB coils.

The FOBs were installed during the night whilst the master ends were all terminated onto CAT6 High Band Frames during the day.

All outlets were tested using our test equipment with DWM cataloguing and presenting the test documentation.

The installation illustrated the need for teamwork amongst our staff, other contractors and the client. It pushed our Project Managers and Site Supervisors to a new level in order to complete the project on schedule, within budget and with the minimum of disruption.